



OHIO811 POSITIVE RESPONSE DEFINITIONS

Here are the response codes that Underground Facility Owner or Operator can provide:

001- No Conflict- Underground facilities operated by this member are not in conflict based on information provided in the Excavation Request.

002- Marked- Underground facilities operated by this member at the site of proposed excavation have been marked up to the privately owned facility.

003- Excavation Request Cancelled (CNCL)- Excavator has cancelled this excavation request.

004- Locator Coordination- Locate request has not been completed. **Locator** has/will contact the excavator to coordinate markings.

005- Facility Owner or Operator Coordination- Locate request has not been completed. **Facility Owner or Operator** will contact the excavator to coordinate markings.

006- High Profile or Critical Facility- Facility Owner or Operator requests to be present for the excavation in accordance with ORC 3781.31 (A). Excavator must provide notification of at least one full working day prior to commencing excavation.

007- Complex Project (LPRJ)- This response is designated for use with a Complex Project notification only.

008- Design Notification (DSGN)- Facility Owner or Operator has completed the design request in accordance with ORC 3781.27 (C) or 153.64 (B) (2).

009- Work Complete- The Facility Owner or Operator or their representatives has deemed the excavation to have been completed prior to the legal start date.

999- No Response (LATE)- The Facility Owner or Operator or its representatives has not posted a Positive Response prior to the legal start date. A "LATE" notification has automatically been sent to the Facility Owner or Operator.